



Selective partial dismantling of Stelling Moor waste incineration plant

Data and facts

Company	PORR Umwelttechnik GmbH in ARGE
Type	Demolition
Runtime	12.2016 - 06.2018
Principal	Stadtreinigung Hamburg AöR

[Project report online](#)

www.porr-group.com



Selective partial dismantling of Stelling Moor waste incineration plant.

The site remediation works comprised asbestos remediation and the treatment of artificial mineral fibres, caustic soda, hydrochloric acid, corrosive residues, hazardous dusts and many other substances. Special black areas were created for the decontamination measures and accordingly sealed off.

Creating value by preserving value.

Most of the approximately 20,000 tonnes of mineral construction waste that remained after the buildings had been demolished were processed on-site by a crushing plant. Part of the reclaimed material was reused in the construction site for technical filling operations. PORR Umwelttechnik removed the excess material professionally and recycled it.

Impressions



Image notes

1

Site of the waste incineration plant in Hamburg.

In 2015, PORR Umwelttechnik was awarded the contract for the selective partial dismantling of the Stelling Moor waste incineration plant.

Do you have questions about the project or would you like to learn more? Feel free to contact us for further information.

PORR AG Group Communications

Absberggasse 47

1100 Wien

T +43 50 626-0

E-Mail: comms@porr-group.com